

GUIDELINE DOCUMENT — FOR ADOPTION

QUALITY STANDARDS & SITE SUPERVISION

DOCUMENT NO. GMF-QS-001	VERSION 1.0 — Draft for adoption	DATE 04 July 2026
APPLIES TO All construction activity on Halls of Worship and ancillary buildings	STATUS Mandatory once adopted	PREPARED BY Vollmann Akarakiri

01. PURPOSE

Weak supervision made past projects hard to control. This document defines **who watches the work, what they check, and how problems are escalated** so that every hall is built to the same benchmark.

02. SUPERVISION STRUCTURE

- A **Site Supervisor / Clerk of Works** is appointed for every active site and is present whenever critical work is executed. They report to the PM — **never** employed by or paid through the Contractor.
- The **design engineers** (structural, MEP) perform stage inspections at the hold points in Section 04 and confirm in writing.

- The **PM** visits site at least monthly and before every gate.

03. DAILY AND WEEKLY RECORDS

Record	Content	Kept by
Site diary (daily)	Weather, labour count, plant on site, work done, deliveries, visitors, instructions given, incidents	Site Supervisor
Weekly site report (GMF-T-02)	Progress vs. programme, photos (minimum 6, dated, consistent viewpoints), issues, look-ahead	Site Supervisor → PM
Site instruction book	Numbered written instructions to the Contractor (no cost effect without a change order per GMF-CM-001 §6)	Site Supervisor
Materials register	Deliveries with quantities, source, and test/quality certificates	Site Supervisor

04. MANDATORY HOLD POINTS

Work **must not proceed past a hold point** until inspected and released in writing on the inspection checklist (template GMF-T-04):

#	Hold point	Released by
1	Setting-out — dimensions and orientation checked against drawings and survey beacons	Site Supervisor + Architect
2	Foundation excavation — depth and bearing stratum vs. soil report	Structural Engineer
3	Foundation reinforcement — size, spacing, cover, before any pour	Structural Engineer
4	Every structural concrete pour (columns, beams, slabs) — formwork, rebar, mix	Structural Engineer or delegated Supervisor
5	DPC / ground floor level before blockwork proceeds	Site Supervisor
6	Roof structure before covering — member sizes, connections, anchorage	Structural Engineer

7	Services first fix before covering up (conduits, plumbing in walls/slabs)	MEP Engineer
8	Waterproofing / tanking before backfill or screed	Site Supervisor
9	Practical completion inspection — full snag list	PM + Design Lead + QS

05. MATERIALS AND WORKMANSHIP BENCHMARKS

All materials comply with the relevant **SON (Standards Organisation of Nigeria)** standards. Minimum controls:

- **Cement:** SON-certified brands only; stored dry off the ground; no set/lumpy cement used.
- **Reinforcement:** mill certificates required per delivery; visibly corroded or undersized bars rejected. Spot-check diameters with calipers.
- **Concrete:** mix design approved by the Structural Engineer before first pour; cube tests (or engineer-approved equivalent) for structural pours — minimum one set per pour day; curing enforced for at least 7 days.
- **Blocks:** from an approved supplier or site-moulded under supervision; crushing test on samples per source; blocks cured before laying.
- **Sand/aggregate:** free of organic material and excessive silt (bottle test on each new source).
- **Roofing, doors, windows, finishes:** samples approved and retained before bulk purchase; installed work is compared against the retained sample.
- **Electrical:** cables and gear SON-certified; all circuits tested and a test certificate issued before energising.
- **Water/plumbing:** pressure test before covering; tanks and borehole installations per manufacturer's data filed in handover records.

Workmanship reference: the drawings and specification extracted from the BIM model are the standard. Where a detail is not specified, the National Building Code applies, and the Design Lead decides.

06. HEALTH, SAFETY AND SITE CONDUCT

- Contractor provides and enforces basic PPE (helmets, boots) for all workers; scaffolding must be sound and inspected weekly.

- Contractor's all-risk insurance and workmen's compensation must be valid before site possession and remain valid throughout (checked monthly by the PM).
- Site secured against unauthorised entry; materials store lockable with a signed issue register.
- Any injury requiring medical attention, structural distress, or statutory stop-order is reported to the PM the **same day** and is an exception event under GMF-PG-001 §5.

07. NON-CONFORMANCE AND ESCALATION

1. Defective work is recorded in a **non-conformance note** (what, where, drawing reference, photo).
2. Contractor proposes remedy; the relevant engineer approves it.
3. Rework is at the Contractor's cost unless a change order says otherwise.
4. Repeated non-conformance (3 notes on the same trade) triggers a formal warning by the PM and is reported to the Board.
5. **Cover-ups without inspection release** (Section 04) are treated as non-conforming and may be ordered opened up at the Contractor's cost.

08. PRACTICAL COMPLETION AND DEFECTS

- Practical completion only when: hold point 9 inspection passed, snag list agreed with completion dates, test certificates delivered, site cleared.
- During the defects liability period the Site Supervisor logs defects reported by hall users; the Contractor remedies within agreed timescales; retention is released only after the final defects inspection (Gate 5).

09. REVISION HISTORY

Version	Date	Change	Author
1.0	04 July 2026	First issue for adoption	Vollmann Akarakiri

AUTHORISATION

PREPARED BY

Vollmann Akarakiri